


All Rights Reserved. Reuse of these documents without the expressed written permission of CARMINA WOOD DESIGN is prohibited. WARNING: It is a violation of article 45 of the state constitution to alter this drawing. If altered such R.A., P.E. or L.L.S. shall affix his or her seal, signature, the date the alteration was made and a specific description of the alteration.

© CARMINA WOOD DESIGN



SKETCH PLAN
SCALE: 1"=40'

TOWN OF AMHERST ZONING CONDITIONS

THE SIX ZONING CONDITIONS IMPOSED BY THE TOWN BOARD ON JULY 22, 2024 IN CONNECTION WITH THE REZONING FROM 'SA' TO 'R-3' WERE AS FOLLOWS

1. THAT FUTURE DEVELOPMENT OF THE SITE SHALL BE LIMITED TO SINGLE FAMILY DETACHED RESIDENTIAL USES WITH A MAXIMUM YIELD OF FIFTEEN (15) HOMES.
2. THAT ANY FUTURE DEVELOPMENT OF A PRINCIPAL OR ACCESSORY STRUCTURE OR USES IN THE 2.7 ACRES OF PERMANENT OPEN SPACE SHALL BE PROHIBITED. THE ONLY PROPOSED DEVELOPMENT OF THE PORTION OF THE PERMANENT OPEN SPACE IS LIMITED TO REQUIRED STORMWATER MANAGEMENT SYSTEM IMPROVEMENTS AND UTILITY INFRASTRUCTURE.
3. THAT A PROTECTIVE COVENANT/CONSERVATION EASEMENT SHALL BE PLACED ON ALL PROPOSED OPEN SPACE AND CONFIRM TOTAL ACREAGE TO BE UNDER THE CONTROL OF A HOMEOWNERS ASSOCIATION.
4. THAT THE FINAL PLAT DESIGN SHALL INCLUDE A RIGHT-OF-WAY ACCESS TO A POTENTIAL FUTURE YOUNGS ROAD EXTENSION.
5. THAT THE LANDSCAPING AND SCREENING TO BE PROVIDED IN THE PERMANENT OPEN SPACE ALONG THE DODGE ROAD FRONTAGE OF THE PROJECT SITE SHALL REQUIRE THE APPROVAL OF THE PLANNING BOARD AT THE PRELIMINARY PLAT APPLICATION STAGE OF THE SUBDIVISION REVIEW PROCESS.
6. ANY FUTURE PRELIMINARY PLAT THAT SHALL BE SUBMITTED TO THE PLANNING BOARD SHALL CONSIDER PROVISIONS FOR FUTURE ACCESS TO THE NORTH AND SOUTH OF THE SUBJECT PROPERTY.

SITE DATA (ZONED R-3)

AREA = 6.7 ACRES ±

MIN. LOT WIDTH = 65 FT INTERIOR LOTS
MIN. LOT WIDTH = 75 FT CORNER LOTS


MIN. LOT AREA = 8,450 SF INTERIOR LOTS
MIN. LOT AREA = 9,750 SF CORNER LOTS

FRONT SETBACK = 30 FT (OFF EDGE OF PVMT)
SIDE SETBACK = 5 FT
REAR SETBACK = 30 FT

MAXIMUM LOT COVERAGE = 35%
MAXIMUM BUILDING HEIGHT = 35 FT

MINIMUM FLOOR AREA = 1,000 SF (1 STORY)
MINIMUM FLOOR AREA = 1,200 SF (2 STORIES)

NOTE: BOUNDARY AND TOPOGRAPHIC INFORMATION PROVIDED BY OTHERS. CARMINA WOOD DESIGN ASSUMES NO RESPONSIBILITY FOR ITS ACCURACY.



REVISIONS:	No.	Description	Date
	1	Rev. Per Town Comments	9/19/2024
	2	Rev. Per Town Comments	10/24/2024
	3	Rev. Per Town Comments	11/11/2024

PRELIMINARY
NOT FOR CONSTRUCTION

DRAWING NAME:
Sketch Plan

Date: 11.11.24
Drawn By: C. Wood
Scale: As Noted

DRAWING NO.
C-100
Project No: 20.247